

LIMITS OF TEMPORARY DEWATERING FOR RAMP CONST.
200#LF COFFER DAM TO BE REMOVED AFTER CONSTRUCTION

HEAVY STONE FILL 30" DEPTH W/GEOTEXTILE

TURBIDITY CURTAIN

30' x 80' SLAB BOAT RAMP PROPOSED CONCRETE


ALUMINUM GANGWAY, HEAVY DUTY (4'x 50')

SECTIONAL FLOATING DOCK (6'x72')

12" WOOD PILE (x4)

KAYAK LAUNCH PORT DOCK (11'x16')

DREDGE AREA TO NAV CHANNEL, MATCH EXISTING AT CHANNEL LINE



- NOTES:**
1. SITE CLEARING AND DEBRIS REMOVAL SHALL BE DONE WITHIN THE ENTIRE DISTURBANCE AREA.
 2. ALL DRAINAGE STRUCTURES TO BE CONSTRUCTED IN ACCORDANCE WITH NYS DOT ITEM 604. REFER TO APPLICABLE NYS DOT STANDARD SHEETS.
 3. SIDEWALKS AND CURB RAMPS SHALL MEET THE CONSTRUCTION REQUIREMENTS AND DETAILS AS SHOWN ON NYS DOT STANDARD SHEET 608-01
 4. ANY CONCRETE DEBRIS LARGER THAN 8", AND OTHER EXCESS MATERIAL SHALL BE NEATLY STOCKPILED ON CITY PROPERTY IMMEDIATELY NORTH OF THE WORK LIMITS, AS DIRECTED BY OWNER.

DATE	REVISIONS RECORD/DESCRIPTION
1	
2	
3	
4	
5	

FRANCIS J. BOSSOLINI PE, PLLC
Land Planning, Civil Engineering
2 Seymour Court, Suite 301
Troy, NY 12180-4825
518-590-4821
518-273-7078 FAX



DRAWN BY: FJB
DESIGN BY: FJB
CHECK BY: FJB
PROJ. NO.: 12-012
SCALE: AS SHOWN
DATE: 05/01/2018

GENERAL PLAN

INGALLS AVENUE BOAT LAUNCH - CITY OF TROY

CITY OF TROY RENSSELAER COUNTY, NY



H₂H ASSOCIATES, LLC
179 RIVER STREET, TROY, NY 12180
518.270.1620

GP-1
SHEET 07 OF 10